

Formular F2

OBIECTIV: 38A Dragomiresi -canaliz pluviala

CENTRALIZATORUL

Nr. cap. / subcap de viz general	cheltuielilor pe categorii de lucrari, pt.obiectul 01 Canalizare pluviala	Valoarea (exclusiv TVA)
		1
		2

4.1. Constructii si instalatii aferente acestora

4.1.1 001 Terasamente

4.1.2 002 Constructii

TOTAL I

TOTAL valoare (exclusiv TVA)

Taxa pe valoarea adaugata

TOTAL valoare (inclusiv TVA)

Intocmit,

Ing. Toma Ion



Formular F3

OBIECTIV: 38A Dragomiresti -canaliz pluviala

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiectul: 01 Canalizare pluviala

Categoria de lucrari: 001 Terasamente

Executant2017 Obiectiv38A Obi01 Cate001

Nr. crt.	Capitolul de lucrari		U. M.	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare
	Simbol	Denumire resursa Observatii Corectii Liste anexe				
SECT IUNE TEHNICA				SECTIUNE FINANCIARA		
0	1	2	3	4	5	
1	TSC02B11	82 SUTE MC		15,50000		
SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39 MC PAMINT UMID.NATUR DESC.DEP.TER.CAT.2 IN COND.GOSP.APE.						
2	TSA02E1	82 M CUB		172,50000		
SAP.MAN.IN SPATII LIMIT.SUB 1M CU TALUZ VERT.NESPR .IN PAM.COEZ.MIJ.SI F.COEZ.ADINC.<1,5M T.MIJL. *						
3	RCSA06B	02 M CUB		910,00000		
UMPLUTURA DE PAMANT, EXEC.IN STR.ORIZ. 20-30CM, UD ATE SI BATUTE CU PLACA VIBRATOARE, INCL.IMPRASTIAT						
4	RCSA06A	02 M CUB		351,00000		
UMPLUTURA DE PAMANT, EXEC.IN STR.ORIZ. 20-30CM, UD ATE SI BATUTE CU MAIUL DE MANA, INCL.IMPRASTIATUL						
5	TRA01A10P	82 TONE		650,00000		
TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.=10 KM						
6	TSD02XB	91 SUTE MC		6,51000		
IMPRASTIEREA PAM.DIN TER.CAT.I-II, CU BULDEZE PE TR CTOR SENILE 65-80CP, IN STRATURI GROS.DE 21-30 CM						
Cheltuieli directe						
Alte cheltuieli directe						
Contrib. asig. munca %						
TOTAL CHELT. DIRECTE						
Cheltuieli indirecte Io = % x To						
Profit Po = % x (To+Io)						
TOTAL GENERAL pe categorii Vo = To+Io+Po						

Intocmit,

Ing. Toma Ion



Formular F3

OBIECTIV: 38A Dragomiresti -canaliz pluviala

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiectul: 01 Canalizare pluviala

Categoria de lucrari: 002 Constructii

Executant 2017 Obiectiv 38A Obi 01 Cate 002

Nr. crt.	Capitolul de lucrari		U. M.	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare
	Simbol	Denumire resursa				
Liste anexe						
SECTIUNE TEHNICA				SECTIUNE FINANCIARA		
0	1	2	3	4	5	
1	ACD04I1	82 BUCATA		20,00000		
CAMIN DE VIZITARE DIN BETON ARMAT PREFABRICAT D100						
0 CU CAPAC FONTA CAROSABIL H=2.9M						
L:10173 -M :2100916 -BETON MARFA CLASA C30/25 (BC30/B400)						
L:10174 -M :2101509 -MORTAR DE CIMENT M100-T						
2	ACD01F1	82 BUCATA		20,00000		
CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE FARA PIES						
A SUPORT CAROSABIL TIP IV \$						
3	ACE02A1	82 BUCATA		23,00000		
GURA DE SCURGERE SIMPLA DIN BETON PREFABRICATA D50						
0 CU GRATAR CAROSABIL						
4	00605E1	02 BUCATA		936,00000		
TEAVA PVC DN 250MM SN8						
lbuc = 1 ml						
L:LA006F1-0078:8815064 -TEAVA CANAL PVC CU MUFA SN8 D=250X7,3MM						
5	00605G11	02 BUCATA		100,00000		
TEAVA PVC DN 200MM SN4						
lbuc = 1 ml						
L:LA006FA-0036:8819186 -TEAVA CANAL PP MULTISTR.MUFA+GARN.SN4 D.200 MM; L=1 M						
6	8814249	M		1036,00000		
BANDA AVERTIZARE CANAL 11,5CM X 0,17MM						
7	ACC11A1	82 BUCATA		40,00000		
INELE ETANSARE CONDUCTE LA CAMINE DE VIZITARE						
8	CA01A1	82 M CUB		100,00000		
BETON SIMPLU C25/30 PT RADIER CAMINE, GURI DE SCUR						
GERE SI PEREU SANT						
L:10173 -M :2100914 -BETON MARFA CLASA C25/20 (BC25/B330)						
9	TRA06A10	82 TONE		240,00000		
TRANSPORTUL RUTIER AL BETONULUI-MORTARULUI CU AUTO						
BETONIERA DE 5,5MC DIST. =10KM \$						
10	ACE08E1	82 M CUB		60,00000		
UMPLUTURA IN SANT LA COND.DE ALIM.CU APA SI CANALI						
ZARE CU BALAST \$						
11	ACE08A1	82 M CUB		351,00000		
UMPLUTURA IN SANT.LA COND.DE ALIM.CU APA SI CANALI						
ZARE CU: NISIP \$						
12	TRA01A10	82 TONE		575,85000		
TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELO						
R CU AUTOBASculANTA PE DIST.= 10 KM. \$						



Executant 2017	Obiectiv 38A	Obi 01	Cate 002		
0	1	2	3	4	5
13	RCSA04B	02 MP		1096,00000	
SPRIJINIRI ORIZONTALE DE MALURI, IN SPATII INGUSTE , L=<1M <20MC, GRELE (INTERSPATII DULAPI 5-20CM)					
14	ACC04D1	82 M		10,00000	
TUB CIRCULAR BETON SIMPLU L=1 M IMBINATE CU MUFA S I ETANSARE UMEDA AVIND DN 400 MM. L:11704 -0004:2804345 -TUB BET.S.CIRC.FARA TALPA CEP SI BUZA 400X1000 S816					
15	DE16A1	82 BUCATA		130,00000	
MONTAREA LA RIGOLE SANTURI A ELEM PREF DIN BETON ARMAT CU VOLUM PINA LA 0,02MC/BUC INCLUSIV L:10823 -M :6350031 -RIGOLA PREFABRICATA					
16	TRA01A10P	82 TONE		117,00000	
TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.=10 KM \$					
Cheltuieli directe					
Alte cheltuieli directe					
Contrib. asig. munca		%			
TOTAL CHELT. DIRECTE					
Cheltuieli indirecte		Io =	% x To		
Profit		Po =	% x (To+Io)		
TOTAL GENERAL pe categorii		Vo = To+Io+Po			

Intocmit,
Ing.Toma Ion

